BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK:Maintenance of UGD in Ward No.12 Shettyhalli, Shettyhalli Sub Division.

Description of work	Unit	Qty	Santioned Rate	
			In Figures (Rs.)	In Words (Rs.)
2	3	4	5	6
1 Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	1441.7	320.86	
2 Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Mtr	1899.87	592.96	
3 Refilling available earth around pipe lines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	984.3	86.17	
4 Providing , laying, spreading and compacting crushed stone aggregates of granite/trap/basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carri etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	260.55	1891.14	
5 Consrtructing brick masnory circular type manhole 0.91 m internal dia at bottom, 0.91m deep and 0.56m dia at top with table moulded bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cem etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Nos	41	15393.28	
6 Disposing off the excess excavated earth of all types upto a distance of 16kms by vehicle including loading,unloading,with all lifts,labour,HOM of machinery etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	457.4	127.50	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner